K-467

Maple Grove Near Langford late 1850's

The site of Maple Grove is one of the most dramatic in the County. Without landscaping or trees, the house is perched on a ridge of ground and can be seen for miles in several directions. Located on the 17th century tract Pentridge, the site slopes primarily to the south. It is likely that the house was constructed in the late 1850's by Laurence M. Strong to replace a previous dwelling in the same location. An earlier house is mentioned in the 1852 Tax Assessment where Strong was taxed on 304 acres of "Scott's Farm" with an "Old House in bad repair." 1

The house which Strong built was not only tall and well-situated, but also built using some of the best catalogue millwork available in the mid-19th century. Like Henry Ward Carvill and several other neighbors, Strong chose the popular Italianate style. The usual features of this style are in evidence in the main part of the house which faces north toward the Langford Road and its lane.

Paneled pilasters are found on each of the four corners of the main block which is three stories tall. At the low-pitched roof there are well-executed brackets. There are also bracketed cornices over each of the windows of the five-bay facade and two-bay ends. Originally there was a balustraded deck atop the roof which afforded extensive vistas in every direction. Like Brampton, there were porches on the front and sides of the house. A two-part 'L' wing out the south side originally contained a dining room, kitchen and pantry with quarters above.

The main house had a central stair plan. Both first floor rooms had jib doors which opened onto the front porch and standard doors to the side porches. The walnut stair ascended to the third floor in a graceful manner so typical of this period.

In the 1877 Atlas, the property is occupied by "J. Rasin."² It was purchased in the 1880's by Thomas W. Eliason, in whose family it remained for 100 years. Most sadly, it has recently been left vacant and open to the elements and is now in derelict condition. Its surrounding farmland is slated for development. If Maple Grove is eventually destroyed the County will suffer a true architectural loss.

- 1. 1852 Tax Assessment.
- 2. 1877 Atlas.

Survey No. K-467

Maryland Historical Trust State Historic Sites Inventory Form

Magi No. 1504675535

DOE __yes __no

1. Nam	e (indicate pr	eferred name)		
historic 01d F	Rasin Farm		a king da Brit	
and/or common	Eliason Far	m		
2. Loca	ation			
At street & number	end of long lane so of Broad Neck Roa		Rd., ½ mile east	not for publication
city, town	hestertown	and a final factor of the	congressional district	1st
state M	laryland	county	Kent	
3. Clas	sification			
Category districtX building(s) structure site object	Ownership public private both Public Acquisition in process being considerednot_applicable	Status occupied unoccupied work in progress AccessibleX yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Own	er of Prope	rty (give names a	nd mailing addresse	es of <u>all</u> owners)
name Elias	son Family c/o T	homas Eliason		
street & number	David Drive		telephone r	10.:301-778-0597
city, town	Chestertown	state	and zip code Mar	yland
5. Loca	ation of Leg	al Description	on	
courthouse, regi	stry of deeds, etc. Ken	t County Court H	ouse	liber EHP53
street & number				folio 7
city, town	Chesterto	wn	state	Maryland 21620
6. Rep	resentation	in Existing	Historical Surv	
title				
date			federal sta	ite county loca
depository for su	urvey records			
city, town			state	

7. Description				<u> </u>	Survey No. K-467		
Condition excellent good fair	X deteriorated ruins unexposed	Check one unaltered altered	Check one original sit moved	e date of move			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

A boxy, rectangular building, this house is 5 bays wide, two deep and three stories tall. It has a central stair, which curves to the third floor, and a rear ell. Covering the main section of this frame house is a shallow hipped roof with a bracketed cornice that was once topped by a widow's walk or belvedere.

8. \$	Sign	ificance		Survey No. K-467	
_ 1500 1600 1700	D-1499 D-1599 D-1699 D-1799 D-1899	archeology-historic agriculture X architecture art commerce	community planning conservation economics education engineering exploration/settlement	literature military music philosophy politics/government	science sculpture social/ humanitarian theater
Specific	dates		Builder/Architect		
check:	aı	icable Criteria:A nd/or icable Exception:A	 -	FG	
	Leve	l of Significance:	nationalstate _	_local	
Prepare	both	a summary paragraph o	of significance and a	general statement of	history and

Now abandoned and deteriorating, this house is one of the best examples of the Greek Revival - Italianate Style houses once common throughout the county. It is exceptionally large - 5 bays wide and three stories tall, and it contains some of the best architectural elements available in builder's catalogues of the middle of the last century. Among these elements are window heads, deeply paneled double entry doors, tall windows with jib doors, a heavily bracketed cornice, and handsome stair. Several examples of original interior finishes enhance the interest of this structure.

9. Major Bibliographical References

Survey No. K-467

10. Geographi	cal Data		
Acreage of nominated property Quadrangle name UTM References do NOT com			Quadrangle scale
Zone Easting No	orthing	B Zone	Easting Northing
C		D	
Verbal boundary description	and justification		
List all states and counties for			
state	code	county	code
11. Form Prep	ared By		
Marsha L. Fritz mame/title Margaret Q. Fal	llaw, Surveyors		
County Commissi			late 5/8/81
organization _{Historical} Soci	<u>iety of Kent Co</u>	ounty	late 5/8/81
The Court House street & numberurch Alley		Juney	778-4600 elephone 778-3499

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House 21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

7.1 DESCRIPTION (continued)

Building Form and Material

- Size Main Section: 3 stories, 5 bays wide, 2 bays deep Wing A: 2 stories, 2 bays wide, 1 bay deep Wing B: 2 stories, 2 bays wide, 3 bays deep/long
- 2. Plan type Central hall with rear ell
- 3. Roof type Main Section: Low Hip
 Wings: A) Very low-pitched gable B) low-pitched
 gable; both change to even lower slope near eave to be able to present
 wide cornice.
- 4. Chimneys-4 Locations: each end of main section (interior); rear gable wall end thru ridge both wings.

Materials: Brick - Main Section is orange-red
Decorative elements: Main Section has corbelled
caps, with mouse-tooth work below; wing chimneys plain (for stoves?)

5. Material/Walls - Main Section: Is Frame with weatherboard with 5"-6" exposure, with recessed-panel pilasters from foundation to cornice line with simple base and capital.

Wing A: Is Frame with weatherboard with 5" exposure

- 6. Material/Roofs Main section: standing-seam metal. So is wing A & B.
- 7. Material/Foundation Main Section: Sides are parged; brick with pilasters at cellar corners

Wing A: Cellar, parged brick
Wing B: Crawl space, parged brick (originally
piers only with brick infill added later)

- 8. Age Main Section: 1850's to 1860's
 Wing A: appears to have been built at same time as the main section
 Wing B: slightly later
- 9. Style Vernacular Greek revival-Italianate

Building Elements and Details

1. Doors - Main Entry: Located in the central bay of the main section; large bracketed hood matching window hoods except longer and 2 additional, smaller brackets; 5 light transom; composite moldings - transom bar; 3-light sidelights over 1 recessed panel with Greek ogee backband;

7.2 DESCRIPTION (continued)

Frame - same as windows. Pair of 3-octogonal-paneled doors with bolection moldings.

Secondary Entries: 1) Located in the rear of central hall of the main section. Stoop or porch removed (was small). 2) Both sides of main section, 1st bay - door to side porch remains but sided over on left side, there may have been similar opening on other side of main section. 3) Wing A: both sides near join with main section; Wing B: center bay both sides.

2. Windows - Main section: type - double-hung
lights - large 6/6 - 1st and 2nd floor
details - narrow muntins; large, bracketed hoods - front and sides; appliques above windows and below hoods;
plain wood sills; wide, one piece, low-relief split face trim (1½
fillet, Greek ogee and bevel, 1-¼" fillet, ½"-5/8" bead)

shutters - louvered; a few shell shutter dogs (2nd floor) remain; thumb-key latch type hardware on others.

Wings: type-double-hung

lights - 6/6 (those of wing A are larger than Wing B's

and same size as Main Section Windows.

details - Wing A: 1" fillet and $\frac{1}{2}$ - 5/8" inside bead; plain sills. Wing B: frame same as Wing A.

shutters - louvered (wing A)-some removed; Wing B - louvered (only one remaining)

- 3. Dormers none
- 4. Roof details Main Section: Heavy scroll-type brackets circa 18-20" on center throughout with applied round medallions, against 14-16" wide fascia; large bevels and square crown molding.

 Wings: WingB Simple box cornice with beveled

Wings: Wing B - Simple box cornice with beveled crown and bed moldings; Wing B - tapered vergeboard at rear gable; Wing A - box cornice with ogee crown molding and no bed molding.

- 5. Porches Removed porch across entire front of house with low hip roof probably original (because of jib doors); there is also evidence of porches along the sides of main section. Wing A small wood porch with shed roof (stoop and 2 steps) appears to have been added in 20th century. Main section side porch appears to have extended over this wing entry. Wing B recent small concrete block and brick stoop and steps with shed overhang of plywood evidence of earlier small, probably wood porch.
- 6. Color Current: white paint and trims; green shutters
 Historic: Siding appears to have been white; main entry
 door Spanish brown; shutters perhaps orange-tan.

7.3 DESCRIPTION (continued)

Interior Description

- 1. Plan type Central hall, one room deep; Rear ell.
- 2. Major stair Beautiful stair open to third floor. Bold, turned newel, eliptical handrail, walnut; turned oak balusters, 2 per step; open-string with leaf-design step brackets. Colors-ochre, risers and baseboard; Spanish brown spandrel; natural railing.

Other stairs - 2, both enclosed, both in wing.

- 3. Major mantles Plain Greek mantel in SE room, first floor. Marbelized slate in round arch in NW room, first floor. Plain marbelized slate mantels on second floor.
- 4. Major trim Windows/doors: Greek ogee and bevel backband, inside bead. Most painted Spanish brown. Trim in NW room, 1st floor, dark brown graining.

Baseboards: 7" board with 2" Greek ogee and bevel. Most painted Spanish brown; in NW room, second floor, upper molding is painted ochre.

Cornices: none Chair rails: none

- 5. Major doors 4-panel doors with applied Greek ogee and bevel panel moldings and shallow raised panels. Most painted Spanish brown. Also some simpler doors also 4-panel and some beaded board doors.
- 6. Floors Random, medium width yellow pine; Most unfinished.
- 7. Walls/ceiling finishes Plaster. In the main stair hall there is a fugitive scroll design in brown on a cream background on walls and ceiling.


Outbuildings/Site Description

- l. Major outbuildings Farmbuildings of varying ages. Are frame none distinctive.
- 2. Site description The siting of this building, a tall building, on the highest rise of ground near makes it visible from miles around on all sides. The house is reached by a long lane. There are no formal gardens remaining and virtually no trees. The cluster of nondescript farm buildings is quite close to the house.
- 3. Views to/from site Surrounding farmlands, rolling hillsides.

7.4 DESCRIPTION (continued)

Use of Building

- 1. Current Abandoned
- 2. Historic Farm residence



SKETCH ROOF PLAN

K-467

OLD (ELIASON FARM)

RASIN
FARM





View to Southwest

OLD RASIN FARM (K-467)

Chestertown, Kent County

Photograph: M. L. Fritz, May 1981